

TC ENERGY CENTER / 12-27-06			
CURRENT SURFACE TO COMPLETION			
REVISED FINAL w/BATHTUB AREA			
NO FILL RETENTION / MAX 16.70 BOTTOM			
PARCEL ID	CUT	FILL	NET
P-1	551	138	413
P-2	497	328	169
P-3	296	976	(680)
P-4	819	2,425	(1,606)
P-5	240	546	(306)
P-6	27	528	(501)
P-7	1,623	867	756
P-8	5,299	1,029	4,270
P-9	140	1,062	(922)
P-10	882	166	716
P-11	50	139	(89)
P-12	101	323	(222)
P-13	274	224	50
P-14	2,585	554	2,031
P-15	398	308	90
P-16	35	327	(292)
P-17	69	615	(546)
P-18	919	22	897
P-19	927	18	909
P-20	33	68	(35)
P-21	1	0	1
P-22	183	1,140	(957)
P-23	70	3	67
P-24	1	1,852	(1,851)
P-25	455	1,773	(1,318)
P-26	0	365	(365)
P-27	44	254	(210)
P-28	195	2,444	(2,249)
P-29	565	1,364	(799)
P-30	355	95	260
P-31	35	0	35
P-32	72	112	(40)

REVISED PROJECT NET  
FILL REQUIREMENT:

429, 965 C/Y

CUT CONTOURS = .2' INTERVALS

FILL CONTOURS = 1' INTERVALS

**MORETRENCH**

...since 1931  
8516 Riverview Dr - Riverview, FL 33569.

**MORETRENCH ENVIRONMENTAL SERVICES, INC.**

Nick Haddon  
11001 Fern Hill Drive  
Riverview, fl. 33569  
Tel: (813) 741-0256  
Fax: (813) 672-4754  
E-Mail: nhaddon@mtacfl.com

**NOTES:**  
CURRENT SURFACE TO COMPLETION

BATHTUB AREAS : NO FURTHER FILL REQ.

RETENTION : NO FILL / MAX 16.70 ELEV

**PROJECT**  
TREASURE COAST ENERGY CENTER

FT. PIERCE, FL



**DRAWINGS PROVIDED BY:**  
Site Tech Solutions  
Site Analysis And Consulting  
Sugarhill Place  
3316 N.E. Sugarhill Ave.  
Suite # 1028  
Jensen Beach, F.I 34957  
Office: 772-225-0909  
Fax: 772-225-0908  
E-Mail: sitetech@bellsouth.net

Drawn By:  
KJH

Checked By:  
JB

Project Number:  
###-###

Est. Number  
ENTER NUMBER

Drawing Number:  
N/A

Sheet: 1 Of 1

PARCEL ID	CUT	FILL	NET
P-33	26	932	(906)
P-34	1	2	(1)
P-35	29	2,047	(2,018)
P-36	0	1,468	(1,468)
P-37	0	817	(817)
P-38	42	411	(369)
P-39	32	2,973	(2,941)
P-40	226	607	(381)
P-41	281	52	229
P-42	24	0	24
P-43	6	489	(483)
P-44	6	1,759	(1,753)
P-45	10	1,548	(1,538)
P-46	21	1,214	(1,193)
P-47	0	872	(872)
P-48	0	1,163	(1,163)
P-49	0	763	(763)
P-50	46	618	(572)
P-51	76	89	(13)
P-52	32	1	31
P-53	9	176	(167)
P-54	18	693	(675)
P-55	287	323	(36)
P-56	1	1,695	(1,694)
P-57	4	1,091	(1,087)
P-58	13	1,107	(1,094)
P-59	89	1,324	(1,235)
P-60	45	314	(269)
P-61	304	760	(456)
P-62	18	596	(578)
P-63	28	348	(320)
P-64	63	516	(453)
P-65	24	2,076	(2,052)
P-66	70	958	(888)
P-67	434	234	200
P-68	215	2,098	(1,883)
<b>TOTALS:</b>	<b>20,221</b>	<b>52,199</b>	<b>(31,978)</b>

