



SITE TECH SOLUTIONS

3316 NE Sugarhill Ave #102B
Jensen Beach, FL 34957

Ph: 772-225-0909
sitetech@bellsouth.net

| Job: SAMPLE (1) | | | | | | | |
|-------------------------------|---------------------|--------------|------------------|-----------------|--------------------------|------------------|------------------|
| AREA & VOLUME REPORT / 0-0-07 | | | | | | | |
| EXISTING vs DESIGN SUBGRADE | | | | | | | |
| REPORT AREAS | | | IN-PLACE VOLUMES | | ADJUSTED VOLUMES | | |
| PARCEL ID | S/Y | ACRES | CUT | FILL | % LOSS | FILL | NET |
| EXCLISLAND / 1 | 74 | 0.02 | 0 | 62 | 20% | 74 | (74) |
| EXCLISLAND / 2 | 41 | 0.01 | 0 | 54 | 20% | 65 | (65) |
| EXCLISLAND / 3 | 139 | 0.03 | 0 | 108 | 20% | 130 | (130) |
| | | | 0 | | | | |
| EXCLISLAND | 254 | 0.05 | | 224 | | 269 | (269) |
| LAKE-EXC / 1 | 28,175 | 5.78 | 62,876 | 3,960 | 20% | 4,752 | 58,124 |
| LOTS / 1-25 | 38,783 | 7.96 | 0 | 38,004 | 20% | 45,605 | (45,605) |
| LOTS / 26-41 | 24,191 | 4.96 | 0 | 23,018 | 20% | 27,622 | (27,622) |
| LOTS / 42-51 | 13,544 | 2.78 | 0 | 15,724 | 20% | 18,869 | (18,869) |
| LOTS / 52-61 | 14,149 | 2.90 | 0 | 15,158 | 20% | 18,190 | (18,190) |
| LOTS / 62-69 | 11,556 | 2.37 | 0 | 11,653 | 20% | 13,984 | (13,984) |
| LOTS / 70-79 | 15,544 | 3.19 | 0 | 16,211 | 20% | 19,453 | (19,453) |
| | | | | | | | |
| LOTS TOTAL: | 117,766 | 24.16 | 0 | 119,768 | | 143,723 | (143,723) |
| PAVE - STD / 1 | 10,130 | 2.08 | 0 | 2,545 | 20% | 3,054 | (3,054) |
| ROAD - EME / 1 | 541 | 0.11 | 0 | 258 | 20% | 310 | (310) |
| SW - STD / 1 | 95 | 0.02 | 0 | 107 | 20% | 128 | (128) |
| SW - STD / 2 | 2,066 | 0.42 | 0 | 994 | 20% | 1,193 | (1,193) |
| | | | | | | | |
| SW TOTAL: | 2,161 | 0.44 | 0 | 1,101 | | 1,321 | (1,321) |
| WETLAND / 1 | 7,201 | 1.48 | 294 | 2,965 | 20% | 3,558 | (3,264) |
| WETLAND / 2 | 2,785 | 0.57 | 1,275 | | 20% | | 1,275 |
| | | | | | | | |
| WETLAND TOTAL: | 9,986 | 2.05 | 1,569 | 2,965 | | 3,558 | (1,989) |
| | | | | | | | |
| REGIONS TOTAL | 169,015 | 34.68 | 64,445 | 130,821 | | 156,987 | (92,542) |
| | | | | | | | |
| UNSPECIFIED | 21,525 | 4.42 | 196 | 7,784 | 20% | 9,341 | (9,145) |
| | | | | | | | |
| JOB TOTAL | 190,539 | 39.10 | 64,641 | 138,605 | | 166,328 | (101,687) |
| | | | | | | | |
| | S/Y | ACRES | C/Y CUT | C/Y FILL | COMP. LOSS | REQ. FILL | NET |
| | SURFACE AREA | | IN-PLACE | | w COMPACTION LOSS | | |

STRIP VOLUMES AND CONSTRUCTION MATERIALS

| SECTIONAL QTY'S | Plane Area | | | Slope Area | | DEPTH | VOLUME |
|------------------------|----------------|---------------|-------------|----------------|---------------|-------|--------------|
| | S/F | S/Y | AC | S/F | S/Y | | |
| EXCLISLAND / 1 | 663 | 74 | 0.02 | 704 | 78 | | |
| EXCLISLAND / 2 | 370 | 41 | 0.01 | 394 | 44 | | |
| EXCLISLAND / 3 | 1,253 | 139 | 0.03 | 1,285 | 143 | | |
| EXCLISLAND | 2,286 | 254 | 0.05 | 2,383 | 265 | | |
| ROAD - EME / 1 | 4,873 | 541 | 0.11 | 4,894 | 544 | 0.67 | 121 |
| SOD - LAKE / 1 | 43,511 | 4,835 | 0.99 | 44,995 | 4,999 | 0.25 | 417 |
| SUBG - STD / 1 | 107,779 | 11,975 | 2.46 | 107,932 | 11,992 | 1.00 | 3,997 |
| SW - STD / 1 | 858 | 95 | 0.02 | 874 | 97 | 0.33 | 11 |
| SW - STD / 2 | 18,595 | 2,066 | 0.42 | 18,964 | 2,107 | 0.33 | 232 |
| SW TOTAL: | 19,453 | 2,161 | 0.44 | 19,838 | 2,204 | | 243 |
| SECTIONAL TOTAL | 177,902 | 19,767 | 4.06 | 180,042 | 20,005 | | 4,778 |

PREDICTED QUANTITIES AND CALCULATIONS ARE BASED UPON COMPUTER GENERATED SURFACE MODELS
 UTILIZING ALL AVAILABLE SUPPLIED INFORMATION ON THE PRINTED PLAN SHEETS AS WELL AS DATA CONVERTED
 FROM THE SOURCE DIGITAL FILES. EXTREME CARE HAS BEEN TAKEN TO INPUT THE SUPPLIED DATA ACCURATELY.
 NO FIELD VERIFICATION OF THE DATA HAS BEEN UNDERTAKEN BY SITE TECH SOLUTIONS.
 NO SPECIFIC WARRANTIES ARE EXPRESSED OR IMPLIED